BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
Bruhat Bengaluru Mahanagara Palike

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of Work: Removal of silt & Repair and maintenance of footpath in new ward no.10 Byatarayanapura.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	2304.00	Supply of Unskilled (Heavy work),Unskilled (Light Work),Sweeper,Billover, Blue Printer, Chief Mazdoor, Labours The wages given below as per Department of Labour, GoK circular vide KAE 83 LMW 2022 dated 13-01-2023 wef 01-04-2023 are listed.for emergency works.	Day	643.40	Rupees Six Hundred Forty Three and Forty Paise Only
2	288.00	Supply of Skilled Mason or Brick layer Class-1 The wages given below as per Department of Labour, GoK circular vide KAE 83 LMW 2022 dated 13-01-2023 wef 01-04-2023 are listed. for emergency works.	Day	676.67	Rupees Six Hundred Seventy Six and Sixty Seven Paise Only
3	1350.00	Earth work excavation by manual means for drains, canals, waste weir, draft, approach channels, key trenches, foundation of Buildings & bridges and such simillar works in all kinds of soils, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. In all kinds of soils Depth upto 1.5 m	Cum	266.20	Rupees Two Hundred Sixty Six and Twenty Paise Only
4	360.00	Providing and laying 100mm thick pre-cast cover slabs over drains &Rain pit of width not exceeding 800 mm using M20 concrete reinforcedwith Micro Alloyed High carbon steel with 3mm - 3ply wired steel @ 2.00 kg/m2, slabs jointed in CM 1:3 proportion and nicely finished Includingproviding holes in the Cover slabs wherever necessary for easy drainageof surface water including of labour, materials, scaffolding, usage of machinery, curing, lead and lift charges etc. Complete.	Sqm	1020.80	Rupees One Thousand Twenty and Eighty Paise Only
5	22.50	Supplying and fixing Pre cast reinforced concrete slab 23cm thick including cost of reinforcement as per design and drawing courses cost of all materials, labour complete as per specifications.	Sqm	5037.00	Rupees Five Thousand Thirty Seven Only
6	240.00	Providing and laying 60mm thick factory made cement concrete paverblock of approved shape and colour of M -30 grade made of C&D wasteby block making machine with vibratory compaction laid in requiredpattern and including over 50mm thick compacted bed of coarse sand,filling the joints with fine sand etc. all complete as per the direction ofEngineer-in-charge.	Sqm	880.00	Rupees Eight Hundred Eighty Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
7	1350.00	Lead for disposal of earth shall be payable at Carriage rates (Lead & Lift) by mechanical means including loading and unloading up to 15kms.	Cum	346.50	Rupees Three Hundred and Forty Six and Fifty Paise Only
8	18.00	Providing and constructing un-reinforced plain cement concrete pavement, thickness as per design, over a preparedsub base, with 43 grade cement or any other type as perClause 1501.2.2 M20 (Grade), coarse and fine aggregatesconforming to IS:383:2016, maximum size of coarseaggregate not exceeding 25 mm, mixed in a concrete mixerof not less than 0.2 cum capacity and appropriate weighbatcher using approved mix design, laid in approved fixedside formwork (steel channel, laying and fixing of 125 micronthick polythene film, wedges, steel plates including levellingthe formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate.	Cum	7011.40	Rupees Seven Thousand Eleven and Forty Paise Only
9	2.00	Supply of Material component Bitumen (emulsion) Rapid Setting RS1* for all road works.	T	47520.00	Rupees Forty Seven Thousand Five Hundred Twenty Only
10	180.00	Supply of Hydraulic Excavator of 0.9 m3 bucket on hire basis including operator, fuel and other incidental charges etc.,	Hr	1485.00	Rupees One Thousand Four Hundred Eighty Five Only
11	480.00	Supply of Tipper-5.5 m3 on hire basis including operator, fuel and other incidental charges etc.,	Hr	1553.20	Rupees One Thousand Five Hundred Fifty Three and Twenty Paise Only
12	150.00	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density	Cum	2814.90	Rupees Two Thousand Eight Hundred Fourteen and Ninety Paise Only
13	40.00	Supply of Material component M-Sand - Fine for all road works.	Cum	1623.60	Rupees One Thousand Six Hundred Twenty Three and Sixty Paise Only
14	40.00	Supply of Material component Granular Aggregates of 12mm downsize for all road works.	Cum	1466.30	Rupees One Thousand Four Hundred Sixty Six and Thirty Paise Only
15	30.00	Supply of Material component Granular Aggregates of 40mm downsize for all road works.	Cum	1309.00	Rupees One Thousand Three Hundred Nine Only
16	300.00	Supply of Material component Cement (OPC/PPC/PSC) for all road works.	Bag	322.30	Rupees Three Hundred Twenty Two and Thirty Paise Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಕಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))